Riverton Builders

640 Mill St, Riverton, VA 23992 | (804) 555-0174

REPAIR ESTIMATE
No. RB-26-212
Date: 2026-10-20

Customer	Thomas Wright
Vehicle / Property	702 Cobblestone Way, Riverton, VA - Hall bath & kitchen ceiling

#	Description	Qty	Unit	Unit price	Amount
1	Mold remediation (containment, HEPA, removal)	48	sq ft	$24.00	$1,152.00
2	Subfloor - remove & replace	40	sq ft	$7.75	$310.00
3	Sister floor joists (rot)	2	ea	$285.00	$570.00
4	Tile floor - remove & replace	52	sq ft	$15.50	$806.00
5	Toilet detach & reset	1	ea	$210.00	$210.00
6	Kitchen ceiling drywall - remove & replace	64	sq ft	$4.60	$294.40
7	Kitchen ceiling paint	180	sq ft	$1.50	$270.00
8	Bathroom vanity - remove & replace (water damaged base)	1	ea	$1,260.00	$1,260.00
9	Baseboard	24	LF	$5.50	$132.00
10	Debris haul	1	ea	$495.00	$495.00
	TOTAL				**$5,499.40**

Notes / Findings

Long-term moisture damage at toilet base. Joist rot at two joists. Mold present beneath tile and on subfloor.

Prices valid 30 days. Hidden damage may require a supplement. Payment is the responsibility of the customer unless the insurer has authorized direct payment in writing.